THE BANK OF MYSORE, LIMITED, BANGALORE.

Statement of the affairs of the Bank of Mysore, Limited, for the week ending 24th March 1927, published under Article 141 of the Articles of Association.

LIABILITIES		Rs.	ASSETS		Rs.
To Capital Receipts	...	20,00,000	By Cash in Hand and at Bankers		24,51,716
,, Reserve Funds	...	15,00,000	,, Loans & Cash Credit Accounts		1,38,04,513
,, Public and other Deposits	...	1,59,82,133	,, Bills discounted	...	2,25,262
,, Sundries	...	1,44,457	,, Investments	....	24,76,382
			,, Balance at Agencies	...	47,166
(Annas and pies omitted.)			,, Dead Stock	...	5,64,795
			,, Sundries	..	56,756
Total	...	1,96,26,590	Total	...	1,96,26,590

BANGALORE,
Dated 29th March 1927.

P. W. O'BRIEN,
Manager.

"I intend moving the honorable the Chief Court to enroll me as an Advocate thereof."

K. M. NAGIAH, B.A., B.L.,
Davangere.

BANGALORE DIVISION.

Dated 25th March 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 7th April 1927 for restoring Bidargere, Doddakere Tank, Regd. No. 20 Anekal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Bidargere Doddakere Tank, R. No. 20, Anekal Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

On acceptance of one of the tenders, the earnest money, on rejected tenders will be returned.

Detailed abstract estimate for restoring Bidargere Doddakere Tank, Regd. No. 20 of Anekal Taluk.

No.	Items of work	Per	Quantity
	BUND.		
1	Earthwork raising bund to R. L. 55·00 ...	C.yd.	7,032
2	Do cutting slopes ...	C.ft.	181
3	Removing and resetting old stone work with new jelly ...	,,	591
4	New stone work	,,	380
5	Jelly wedging to old stone revetment	C.yd.	248
6	Turfing	Sqr.	8,094
7	Removing, refixing old grade stones after cutting figures and painting.	No.	17
8	Preparing and fixing new grade stones including painting and figurings.	,,	13
9	Index stones	,,	30
10	B. M. Stones, painting and figuring old	,,	2
11	Registered No. stone (painting and figuring) old ...	L.S.	Rs.
12	Gauge stones new	,,	Rs.
13	Removing and hills and refilling with sand... ...	No.	15
	SLUICE No. 1.		
1	Earthwork cutting bund for examining sluice and refilling with consolidation.	C.yd.	177
2	Repairing the leaks in the sluice and providing plug rod and locking arrangements, etc., complete.	L.S.	Rs.
	SLUICE No. II.		
1	Earthwork cut opening the bund and examining the sluice and refilling with watering and tamping, etc.	C.yd.	295
2	Blocking up old sluice with masonry, etc. ...	L.S.	Rs.
3	Surki concrete filling	C.ft.	302
4	Burnt brick in surki mortar	,,	394
5	Burnt stone slabs 6" thick roughly dressed	S.ft.	307
6	Plastering with surki	Sqr.	3·81
7	Rough surki plaster	,,	2·34
8	Cement pointing	,,	0·55
9	Dressing and drilling orifice	No.	1
10	Providing plug with iron rod etc., complete ...	L.S.	Rs.
11	Dismantling old orifice	,,	Rs.
12	Forming ring bund and baling water	,,	Rs.
13	Removing and rebuilding old stone work	C.yd.	7
14	New stone work	,,	9
	WASTE WEIR No. 1 LEFT 46' LONG.		
1	Earthwork excavation weir and using for flanks ...	C.yd.	163
2	Dismantling the existing upright and using as pin slabs	L.S.	Rs.
3	Surki concrete	C.ft.	175
4	Burnt brick in surki mortar	,,	340
5	Burnt stone slabs 6" thick	S.ft.	245
6	Removing and resetting old stone work with new jelly ...	C.yd.	37
7	New stone work	,,	62
8	Plastering with surki	Sqr.	4·53
	WASTE WEIR No. II RIGHT.		
1	Earthwork	C.yd.	18
2	Surki concrete	C.ft.	35
3	Burnt brick in surki mortar	C.ft.	125
4	Surki plastering	Sqr.	1·61
5	Cement plastering	,,	0·90
6	Rough stonework new	C.yd.	3
7	Do old	,,	2

R. W. SCALDWELL,
Executive Engineer.